CHESTER AV

E.A.

4" W. PIPE

3980 3979 3953 3954 3955 3978 3977 3956 3976 3957 3975 3958 3974 3959 3973 3960 3972 3961 3971 3962 3970 3963 3969 3964 3968 3965 3967 3966

M Y R T L E A V E.

3934 3935 3932 3931 3930 3929 3928 3927 3926 3925 3924 3923 3922 3921

74

2

2 R.R. SIDINGS

THE MANSFIELD ELEVATOR CO.

2

COAL NO.

DEC. 1914
MANSFIELD
OHIO

60'

12" W. PIPE

D.H.

THE MANSFIELD ELEVATOR CO.
GOEMANN GRAIN CO., OWNERS
ELEVATOR CRIB CONSTRN:- CAPCY. 130000 BUSHEL:- BUILT 1902
NIGHT & SUNDRY WATCHMAN:- A.T.U.
SYSTEM REPORTS HOURLY TO 2 STATIONS
LIGHT:- ELECTRIC I.C.E.R. POWER & HEAT:- STEAM
FUEL:- COAL:- WINTER CASKS & PAILS DIST'D.-
MACHINERY:-
1: B & L. OAT CLIPPER-1: B & L. SEPARATOR-
1: CORN SHELLER:-

CORP'S SHOP
FRAME
ENG. & BO'R
BRICK
UNKNOWN STEAM ATTACHMENTS
BRICK
3 SM. GRAIN CONVEYORS APP. FROM TRANSFER HOUSE
TRANSFER HOUSE
(CORR. IR CL.)
IR. CL.
TUNNEL
OFF. IR CL.
JACK SHAFT
JACK SHAFT

16 CONCRETE GRAIN TANKS 28' X 56' 140000 BUSHELS

PENNSYLVANIA LINES W. OF PITTSBURG

L.E.W. & W. R.R.

B. & O. R.R.

TRANSFER TRACKS

C. & P. R.R. (FT. WAYNE ROUTE)

5

28

DAISY

MICHAEL REIMER'S SUBDIV'N.

5277 5278 5279 5280 5281 5282 3911 3912 3913

5914 5915 5916 5917 5918 5919 5920

WATCHMAN:- LIGHTS:- ELECTRIC:- POWER:- GAS
ENG. 125 H.P. HEAT:- STOVES:-
ROCKWOOD AUTOMATIC SPRINKLERS
SINGLE SOURCE, DRY PIPE SYSTEM:- CITY WATER
6" GUNM:- ABOUT 165:- HEADS SPACED 9' & 8', 100
LBS. PRESS:- OUTSIDE SPRINKLER ALARM:-
6:- PYRENE & 1:- CHEM. FIRE EXTGR:-

THE MANSFIELD ELEVATOR CO. OFFICE

EXCELSIOR MFG. CO. (IR. CL.)

GAS ENG.

PICKER NO.

PICKER NO.

OFFICE NO.

THE BALYEAT MFG. CO.
MATTRESS FACTORY

12" W. PIPE

N. MAIN

LILY

HARKER

ORCHARD

D.H.

1882 1881 1880 1879 1878 1877 1876 1875 1874 1873

JOHNS ADD'N.

2165 2166 2167 2168 2169 2170 2171 2172 2173 2174

EXTENSION OF BERTIE JOHNS ADD'N.

STOCKING'S

5264 5263 5262 5261 2056 2055 2054 2053 2052 2051 2037 2036

F. SMITH'S SUBDIV'N.

B. T. MATCH CO.
MAN ABOUT PLANT OFF & NIGHT:- LIGHT & POWER:- ELECTRIC:- HEAT:- STEAM:- SMALL AMOUNT OF HOSE:-

OFF. IR CL. MATCH & WAKING & PACKING 2A

MIXING RM.

ADD'N.

GOLDEN GATE

4

Scale of Feet.

50 40 30 20 10 0 50 100 150

4" W. PIPE

6" W. PIPE

6" W. PIPE

4" W. PIPE

4" W. PIPE

D.H.

D.H.

D.H.

D.H.